Implementation of the CDM 2015 Principal Designer Role

Dr Mike Webster BEng MSc PhD DIC CEng FICE FIStructE

DIOHAS Meeting

11th September 2023

Construction and Structural Safety | CDM | Risk | Regulatory



Agenda for today

• Brief overview of the PD Review

- Issues that may require further focus
- Q&A

Overview of the PD Review


- HSE tender Dec 2020 with review to be completed by 31 March 2021
- Online survey (849 respondents)
 - Implementation of each relevant CDM 2015 clause on a project (c500)
 - Behaviours that influence the PD role (c360)
 - Comments on what's working and what's not (c320)
- Interviews with & written submissions from 20 key stakeholders
- Two Reports
 - HSE Research Report 1198 (https://www.hse.gov.uk/Research/rrhtm/rr1198.htm)
 - Technical Annex (<u>http://mpwrandr.co.uk/implementation-of-the-cdm-2015-principal-designer-role/</u>)
- Authors of HSE Research Reports are not allowed to make recommendations for HSE / Government Policy in those reports

Issues that may require further focus

The need for more designer-led design risk management

- Designer-led design risk management embeds the Principal Designer (PD) role in design organisations
- Increased awareness of the implications of design decisions on construction, other use and maintenance
- Emphasis on preconstruction planning and information

Additional role undertaken by PD



29/02/2023-09-11-DIOHAS CDM 2015 PD v1.0 11 Septem

MPWR&R 4

Appointing the right people at the right time with the right resources

- Right people
 - PD role requires a broad range of skills, knowledge, and experience plus credibility and 'soft skills'
 - Proper integration of PD into projects is essential
- Right time
 - Some clients appoint PDs late, hindering their influence
- Right resources
 - Commercial pressures impacting on the PD role were reported in a range of circumstances

The current understanding of the PD role is not always sufficient

- Clients and PDs sometimes misunderstand the PD role
- Need for guidance and clarity, especially on smaller projects
- Various issues causing confusion and barriers to implementation

Some PDs not empowered or given authority to undertake role and may not be 'in control' of preconstruction phase

- Empowerment & Authority
 - PDs need authority and empowerment such as control over budgets
 - Collaboration between PDs, design teams, and client support is crucial
 - Lead Designer better placed
- Control Regulation 5(1)(a)
 - 20% did not consider PD to be in control of pre-construction phase
 - Reasons for lack of control linked to culture and contracts
 - D&B contracts present particular issues

PDs interaction with temporary works needs to increase

- 38% indicated that PD interacted with Temporary Works Designers
- PDs needs to establish effective dialogue with PC's Temporary Works Coordinator to coordinate temporary works design
- PDs should consider PCI required by Temporary Works Designers in addition to Permanent Works Designers
- PDs had lacked sufficient knowledge of temporary works and the construction process
- PDs temporary works duties better defined than other duties

Procurement routes & forms of contract influence how the PD role is undertaken

- Challenges related to PD role and standard industry contracts
- Considerations in Design and Build projects
- Impact of different contractual situations

Some organisations are more willing to undertake the PD role than others

- Designers
 - Liability of 'coordination for health and safety' even though they are coordinating the design
 - Cost of PI insurance
 - Health and safety seen as a Contractor's role
- Contractors
 - Contractor would have to 'outsource' the day-to-day PD activities to an advisor
 - To reduce Contractors' statutory liabilities
 - Contractor genuinely does not understand what is required of PD role


The PD is perceived by some to be a low value role

- Low PD fee levels and their impact
- The role of inexperienced PDs in reinforcing a box-ticking mentality
- The need for evidence of the PD role's value

Not all those with PD duties have integrated the PD role within their organisation

- Still organisations who appointed advisors to help rather than integrate it within their business
- PD is not integrated in the Lead Designer's team because:
 - PD appointed by the Client, but D&B Contractor runs the design via its Design Manager which limits the PD's contact with Designers in supply chain
 - PD does not have key staff from traditional technical design professions
 - PD lacks the knowledge to enable proper integration in the design team across all parts of the project.

The potential value of BIM is only being realised on larger projects – likelihood of use influenced by ...



Summary

- 1. The need for more designer-led design risk management
- 2. Appointing the right people at the right time with the right resources
- 3. The current understanding of the PD role is not always sufficient
- 4. Some PDs not empowered or given authority to undertake role and may not be 'in control' of preconstruction phase
- 5. PDs interaction with temporary works needs to increase
- 6. Procurement routes & contract form influence how PD role is undertaken
- 7. Some organisations more willing to undertake the PD role than others
- 8. PD is perceived by some to be a low value role
- 9. Not all with PD duties have integrated PD role within their organisation
- 10. The potential value of BIM is only being realised on larger projects

Any questions?

About the Author

| | Profile | In recent years |
|-------------------------------------|---|---|
| | Mike has over 30 years' experience. He specialises in construction and structural safety, CDM and risk, and founded MPW <i>R&R</i> to provide Consulting, Forensic and Expert Witness services in those areas. | Mike has specialised in construction health & safety, risk and the CDM Regulations; heProvided support to HSE in the revision of the CDM |
| | | 1994 ACoP and Guidance; |
| Dr Mike Webster | He is a member of the Temporary Works forum, Structural- | Led a review of HSE's Designer Initiatives; |
| BEng, MSc, PhD, DIC, CEng, FICE, | Safety, Confidential Reporting on Structural Safety and the Institution of Structural Engineers Health and Safety Panel. | Led independent evaluations of CDM 1994 investigating industry practices and costs of compliance – this |
| FIStructE | Mike has: | informed HSE's development of CDM 2007; |
| Director, MPW | Worked on the design, appraisal, repair and site | Led the independent evaluations of CDM 2007, |
| R&R | supervision of building and bridge structures; | Led the review of the use of CDM 2007 in the |
| Contact: | Developed guidance for assessing the safety of existing | construction of London 2012;Led the recent review of the Principal Designer role |
| 07969 957471 | structures in the UK, EU and HK; | |
| mike.webster@mp | • Expertise in construction health and safety and CDM | Has been instructed as an expert witness by both process the second defense teams in cases involving |
| wrandr.co.uk http://mpwrandr.co. | gained from undertaking a range of projects for HSE, advising duty holders and acting as an expert witness; | prosecution and defence teams in cases involving allegations of corporate and gross negligence manslaughter and breaches of the Health and Safety at |
| <u>uk</u> | | |
| https://www.linkedin | Authored of >50 published reports and papers on a range of risk topics <u>http://mpwrandr.co.uk/publications/</u>; and | Work Act and the ODW Regulations, and |
| .com/in/mikewebste | Authored nearly 30 blog posts on construction safety, | • Has provided opinion on cases involving collapses, falls |
| rmpwrandr/ | structural safety and risk (<u>http://mpwrandr.co.uk/blog/</u>). | from height, temporary works, fire, etc. |
| | | |

MPW*R*&*R* | 16